

## M50 RUBBER/ PLASTICS/ CORK / LINO / CARPET TILING / SHEETING

### 110 - Resilient Floor Tiling InstaFloor/Innov8Floors LINO DL MAGNAFLOOR

#### 110 RESILIENT FLOOR TILING

##### LOCATION

Heavy use areas - Office, Retail, Hospitality, Educational and Residential areas.

##### BASE

Refer to InstaFloor/Innov8Floors installation instructions.

##### PREPARATION:

Sub-floors should be prepared in accordance with BS 5325, BS 8203, BS 8204, BS 8201 and BS 8425 or other relevant Standards.

##### FABRICATED UNDERLAY:

Ezy-Install 2.5mm Magnetic Installation System loose laid to sub floor creating floating floor.

##### PRODUCT REFERENCE:

##### LINO DL MAGNAFLOOR

- Thickness: 4mm
- Backing Type: Cork Composite + Magnafloor Magnetic Layer
- Weight (kg/m<sup>2</sup>): 4
- Tile Size: 390mm x 620mm / 200mm x 1235mm
- Dimensional Stability EN434: < 0.05%
- Thermal Resistance EN 12524 (m<sup>2</sup> K/W): 0.06
- Impact Sound  $\Delta$  Lw: 16dB
- Classification EN16511: Domestic 23 / Commercial 33
- Reaction of fire EN ISO 9239-1: Cfl s1 (B1)
- Coefficient of friction EN51130: R10

##### MANUFACTURER:

InstaFloor t/a InstaCoustic Ltd, Insta House, Ivanhoe Road,  
Hogwood Business Park, Wokingham, Berkshire, RG40 4PZ

Tel: 0118 973 9560

Email: [sales@instafloor.co.uk](mailto:sales@instafloor.co.uk)

Web: [www.instafloor.co.uk](http://www.instafloor.co.uk)

## M50 RUBBER/ PLASTICS/ CORK / LINO / CARPET TILING / SHEETING

### 110 - Resilient Floor Tiling InstaFloor/Innov8Floors LINO DL MAGNAFLOOR

#### GENERALLY

##### 210 WORKMANSHIP:

- All bases must be rigid, dry, sound, smooth and free from grease, dirt and other contaminants before coverings are applied.
- Installation should be carried out in strict accordance with the InstaFloor/Innov8Floors installation instructions

##### 320 STORAGE:

Store materials in a clean, warm, dry, well ventilated location. Keep in original packing until conditioning commences.

##### 330 COMMENCEMENT:

Do not lay materials until building is weathertight, wet trades have finished their work, the building is well dried out, all paintwork is finished and dry.

##### 340 CONDITIONING:

Before laying commences thoroughly condition materials by unpacking and separating in the spaces where they are to be laid. Minimum conditioning time and temperature to be as recommended by InstaFloor/Innov8Floors. Extend period by a factor of 2 for materials stored or transported at a temperature of less than 10°C immediately prior to laying.

##### 350 ENVIRONMENT:

Before, during and after laying, provide adequate ventilation and maintain temperature and humidity approximately at levels which will prevail after the building is occupied.

##### 360 UNDERFLOOR HEATING:

Strictly follow the InstaFloor/Innov8Floors underfloor heating installation instructions for the type of resilient floor covering being installed.