

K21 – WOOD STRIP / BOARD FINE FLOORING / LININGS

110 Wood Flooring InstaFloor/Innov8Floors Timber-475 MAGNAFLOOR

110 WOOD FLOORING

LOCATION

Heavy use areas - Office, Retail, Hospitality, Educational and Residential areas.

BASE

Refer to InstaFloor/Innov8Floors installation instructions.

PREPARATION:

Sub-floors should be prepared in accordance with BS 5325, BS 8203, BS 8204, BS 8201 and BS 8425 or other relevant Standards.

FABRICATED UNDERLAY:

Ezy-Install 2.5mm/3mm Magnetic Installation System loose laid to sub floor creating floating floor.

PRODUCT REFERENCE:

Timber-475 MAGNAFLOOR

- Thickness: 13mm
- Wear Layer: 3.6mm
- Backing: Magnetic backing layer
- Weight (kg/m²): 9.6 kg/m²
- Plank Sizes: 125mm x 750mm / 125mm x 1800mm
- Thermal Resistance EN 12524: 0.019 m² K/W
- Impact Sound: 16dB Δ Lw
- Reaction of fire EN ISO 9239-1: Cfl s1
- Coefficient of friction EN51130: R10

MANUFACTURER:

InstaFloor t/a InstaCoustic Ltd, Insta House, Ivanhoe Road,
Hogwood Business Park, Wokingham, Berkshire, RG40 4PZ
Tel: 0118 973 9560

Email: sales@instafloor.co.uk

Web: www.instafloor.co.uk

K21 – WOOD STRIP / BOARD FINE FLOORING / LININGS

110 Wood Flooring

InstaFloor/Innov8Floors Timber-475 MAGNAFLOOR

GENERALLY

210 WORKMANSHIP:

- All bases must be rigid, dry, sound, smooth and free from grease, dirt and other contaminants before coverings are applied.
- Installation should be carried out in strict accordance with the InstaFloor/Innov8Floors installation instructions

320 STORAGE:

Store materials in a clean, warm, dry, well ventilated location. Keep in original packing until conditioning commences.

330 COMMENCEMENT:

Do not lay materials until building is weathertight, wet trades have finished their work, the building is well dried out, all paintwork is finished and dry.

340 CONDITIONING:

Before laying commences thoroughly condition materials by unpacking and separating in the spaces where they are to be laid. Minimum conditioning time and temperature to be as recommended by InstaFloor/Innov8Floors. Extend period by a factor of 2 for materials stored or transported at a temperature of less than 10°C immediately prior to laying.

350 ENVIRONMENT:

Before, during and after laying, provide adequate ventilation and maintain temperature and humidity approximately at levels which will prevail after the building is occupied.

360 UNDERFLOOR HEATING:

Strictly follow the InstaFloor/Innov8Floors underfloor heating installation instructions for the type of resilient floor covering being installed.